

Claim 1 (Canceled).

Claim 2 (Currently amended): The apparatus of claim [[1]] 31 in which the perimeter structural support means comprises a retaining wall.

Claim 3 (Currently Amended): The apparatus of claim 2 in which the means for draining run off water from the [[liner]] holding means includes a dry well.

Claim 4 (Currently Amended): The apparatus of claim [[1]] 31 in which the means for draining run off water from the [[liner]] holding means includes a pump.

Claim 5 (Currently Amended): The apparatus of claim [[1]] 31 in which the perimeter structural support means includes a plurality of caissons.

Claim 6 (Currently Amended): The apparatus of claim 5 in which the perimeter structural support means further includes an L-beam disposed on at least some of the plurality of caissons.

Claim 7 (Currently Amended): The apparatus of claim 5 in which each caisson of the plurality of caissons [[are]] is spaced apart from each other caisson.

Claim 8 (Original): The apparatus of claim 7 in which the plurality of spaced apart caissons includes a first row of spaced apart caissons and a second row of spaced apart caissons.

Claim 9 (Currently Amended): The apparatus of claim 8 in which the perimeter structural support means includes a first L-beam disposed on the first row of spaced apart caissons and a second L-beam disposed on the second row of spaced apart caissons.

Claim 10 (Original): The apparatus of claim 9 in which the roof means comprises a plurality of tee elements disposed on the first and second L-beams.

Claim 11 (Currently Amended): The apparatus of claim ~~[[1]]~~ 31 in which the roof means includes a plurality of tee elements disposed on the perimeter structural support means.

Claim 12 (Previously Amended): The apparatus of claim 11 in which the plurality of tee elements are disposed adjacent to each other.

Claim 13 (Currently Amended): The apparatus of claim ~~[[1]]~~ 31 in which the ~~[[liner]]~~ holding means includes an upper side wall portion, a lower side wall portion, and a bottom portion.

Claim 14 (Original): The apparatus of claim 13 in which the upper side wall portion is disposed at a relatively shallow angle.

Claim 15 (Original): The apparatus of claim 14 in which the lower side wall portion is disposed at a relatively steep angle.

Claim 16 (Currently Amended): The apparatus of claim ~~[[1]]~~ 31 in which the ~~[[liner]]~~ holding means comprises a plastic liner.

Claim 17 (Currently Amended): The apparatus of claim ~~[[1]]~~ 31 in which the ~~[[liner]]~~ holding means is made of cementitious material.

Claim 18 (Currently Amended): The apparatus of claim ~~[[1]]~~ 31 in which the perimeter structural support means includes a generally vertically disposed retaining wall.

Claim 19 (Currently Amended): The apparatus of claim 18 in which the
[[liner]] holding means is secured to the vertically disposed retaining wall.

Claim 20 (Original): The apparatus of claim 19 in which the retaining wall is
relatively short.

Claim 21 (Original): The apparatus of claim 19 in which the retaining wall is
relatively long.

Claim 22 (Currently Amended): The apparatus of claim [[1]] 31 in which
the perimeter structural support means includes a stepped retaining wall.

Claim 23 (Currently Amended): The apparatus of claim [[1]] 31 in which the
perimeter structural support means includes a plurality of relatively short stepped
retaining walls.

Claim 24 (Currently Amended): The apparatus of claim 23 in which the
[[liner]] holding means is secured to the plurality of relatively short stepped retaining
walls.

Claim 25 (Currently Amended): The apparatus of claim ~~[[1]]~~ 31 in which the roof means includes a plurality of structural tee elements.

Claim 26 (Previously Amended): The apparatus of claim 25 in which the roof means further includes a concrete cap disposed on the plurality of structural tee elements.

Claim 27 (Canceled):

Claim 28 (Currently Amended): The apparatus of claim ~~[[27]]~~ 32 in which the means for draining run off water from the ~~[[liner]]~~ holding means includes a dry well.

Claim 29 (Currently Amended): The apparatus of claim ~~[[27]]~~ 32 in which the means for draining run off water from the ~~[[liner]]~~ holding means includes a pump.

Claim 30 (Currently Amended): The apparatus of claim ~~[[27]]~~ 32 in which the ~~[[liner]]~~ holding means comprises a plastic liner.

31 (New): Underground water retention apparatus comprising in combination:
means for providing perimeter structural support;
means for holding a quantity of run off water secured to the means for providing
perimeter structural support;
means for draining run off water onto the means for holding a quantity of run off
water;
means for draining run off water from the means for holding a quantity of run off
water; and
means for providing a roof for covering the holding means, and for providing
structural support for appropriate use of this roof means, disposed on the perimeter
structural support means.

32 (New): Underground water retention apparatus comprising in combination:
 means for providing perimeter structural support, including a plurality of spaced
apart caissons;
 means for holding a quantity of run off water secured to the means for providing
perimeter structural support;
 means for draining run off water onto the holding means;
 means for draining the run off water from the holding means; and
 means for providing a roof for covering the holding means, and for providing
structural support for appropriate usage of this roof means, disposed on the perimeter
structural support means.